

As part of Southeastern Pennsylvania Transportation Authority (SEPTA) Rebuilding the System program, improvements to Stadium Station in Radnor Township included new high-level accessible platforms, customer shelters, retaining walls, signage & lighting upgrades, landscaping and fencing.

Stadium–Ithan Avenue station, formerly known as Stadium station serves the Norristown High Speed Line and is located on Ithan Avenue near Villanova University Stadium.

Brayman Precast from Saxonburg, PA in conjunction with Sandra Palone & Associates fabricated and delivered 123 pieces of precast concrete to the job site. The components included custom precast concrete platforms with tactile warning pads that feature stenciling, precast concrete pier caps, foundations, ramps, stairs, landings and infill panels.

The improvement project modernized the Stadium Station in order to provide accessibility for all users. Precast concrete components replaced the old infrastructure that was in need of repair.

TAKE A NEW LOOK AT PRECAST

Pennsylvania Precast Association • www.paprecast.org

Info@paprecast.org

© 2020 PPA

PRECAST CASE STUDY

PROJECT:
SEPTA IMPROVEMENT PROJECT AT
STADIUM ITHAN AVENUE STATION

LOCATION:
VILLANOVA, PA

PRECAST MANUFACTURER
BRAYMAN PRECAST
www.braymanprecast.com

